



Stadium Roof Lifting at Bilbao, Spain



Facts

Distance lifting and tensioning:	50 m
Duration of lifting:	3 we

Handling equipment

Strand jacks H-40:	96 pcs
Strand jacks H-70:	40 pcs
Strand jacks H-140:	24 pcs

Description

For the 50'000 spectators San Mamés Stadium at Bilbao, Spain, Hebetec Engineering Ltd. was assigned to lift the rope support structure for the inner roof construction

The ground floor assembled structural rope was lifted and tensioned with strand jacks arranged at two levels.

During operations the 160 strand jacks applied for this job were monitored by a camera system.

